



COMPACT END CANTILEVER TOWER SCAFFOLD

3T - Through the Trapdoor Method

USER GUIDE

Contents

Safety First	2
Component Diagram	12
Component Quantity & Safety Data Schedule	13
Build Method	17
Pre-use Safety Inspection Checklist	30

Introduction

Please read this guide carefully.

Please note that diagrams are for illustrative purposes only.

User guides are also available to download from our website at www.bossaccesstowers.com

BoSS mobile aluminium towers are light-weight scaffold towers used throughout the building and construction industry for both indoor and outdoor access solutions where a stable and secure platform is required. Ideal for maintenance and installation work or short-term access, the highly versatile towers provide a strong working platform for a variety of heights.

The law requires that personnel erecting, dismantling, using or altering towers must be competent. Any person erecting or using a BoSS mobile tower must have a copy of this user guide. For further information on the use of mobile access and working towers consult the PASMA operators code of practice.

Verification and assessment documentation is held by Werner Sales & Distribution Ltd.

If you need further information, design advice, additional user guides or any other help with this product, please contact the manufacturer on +44 (0)1621 745900 or email uk.customercare@wernerco.com.


Safe use

- Check overhead that the area into which the structure is to be erected contains no obstructions, particularly electrical or radio radiation hazards.
- The structure is highly conductive and must not be used when there is a risk of lightning strikes.
- Ensure the ground on which the mobile access tower is to be erected is capable of supporting the tower in use.
- Before each use:
 - Check that each prefabricated tower scaffold is complete and correctly assembled.
 - Check that the prefabricated tower scaffold is vertical and make any adjustments as required.
 - Check that no environment changes will affect the safe use of the structure.
- Adjustable legs should only be used for levelling purposes and never to gain extra height.
- Do not use ladders, steps, boxes or similar, to gain additional working height.
- Only climb the tower from the inside using the access method provided.
- Tower scaffolds are not designed to be lifted or suspended.
- Beware of horizontal forces (e.g. power tools) which could generate instability.

Maximum horizontal force per working bay = 30kg

- Tools and materials should be lifted using a reliable lifting material (e.g. a strong rope) employing a reliable knot (e.g. clove hitch) to ensure safe fastening and always lift within the footprint of the prefabricated tower scaffold (i.e. within the area bounded by the stabilisers).
- Use good manual handling techniques when handling tower components.
- Safe working loads, normally expressed in kN/m², are expressed on the page opposite in kg per defined working area.

Safe use



1.8m l	ong main tower with 0.75r	n long cantilever	
Defined working area	Max. safe working load (uniformly distributed including persons)	Load class	Max. no. of persons*
AxZ	416 kg		
BxZ	275 kg	3	1
CxZ	691 kg		

2.5m	ong main tower with 0.75r	n long cantilever	
Defined working area	Max. safe working load (uniformly distributed including persons)	Load class	Max. no. of persons*
AxZ	586 kg		
BxZ	275 kg	3	1
CxZ	861 kg		

^{*}Persons are assumed to be 122kg (Reference to HSE - Revision of body size criteria in standards Protecting people who work at Access Classes height - Research report 342)

Access classes

The Access Class provided for climbing this tower is: Access Class 'D' (Vertical Ladder).

Lifting of individual tower components

 Raising and lowering components, tools and/or materials by rope should be conducted within the tower base (i.e. within the area bounded by the stabilisers). Ensure that the safe working load of the supporting decks and the tower structure is not exceeded.

Movement of the assembled prefabricated tower scaffold

Ensure gloves or other suitable hand protection is worn.

Before

The safe movement of any prefabricated tower scaffold should be included in a specific risk assessment and take into account:

- Ground surface (such as potholes, unstable surfaces, inclines).
- Overhead obstructions (such as live electrical cables or building members).
- Wind conditions
- Dimensions of the tower structure (a shorter tower will be more stable during movement - see PASMA guidance).
- Consequences of overturning.

If the site conditions are not adequate to permit the safe movement of a mobile tower structure, then it must not be moved.

During

Mobile tower structures should be moved with the utmost caution:

- Remove cantilever by reversing assembly steps 12, 11 and 10.
- Remove ballast.
- Any stabilisers fitted must remain in position and raised no more than 25mm from the ground.
- Prefabricated tower structures must only be pushed using manual effort at or near the base.
- Movement of a mobile tower structure shall be no faster than 0.25m/s (very slow walking pace) and sufficient number of persons shall be used to ensure the movement is fully under control.
- No persons, tools or materials shall be left on the mobile tower structure during movement.

Movement of the assembled prefabricated tower scaffold

- Ensure all castors are unlocked.
- Beware of ground level and overhead obstructions, uneven or sloping ground, sudden changes of levels (holes, voids, kerbs).

After

- Ensure all castors are locked.
- · Reposition stabilisers as per assembly step 6.
- Replace ballast as per assembly step 7.
- Replace cantilever as per assembly steps 10, 11 and 12.
- The pre-use checklist on the final page shall be used to determine tower integrity.

Maintenance - Storage - Transport

- All components and their parts should be regularly inspected to identify damage, particularly to joints. Lost or broken parts should be replaced and any tubing with indentation greater than 5mm shall be replaced. Adjustable leg threads should be cleaned and lightly lubricated to keep them free running.
- Brace claws, frame interlock clips, trapdoor latches, camlocks and platform wind-locks should be regularly checked to ensure they lock correctly.
- Refer to the BoSS Inspection Manual for detailed inspection and maintenance advice: www.bossaccesstowers.com
- Components should be stored in clean, dry conditions with due care to prevent damage.
- Ensure components are not damaged by excessive strapping forces when transported.

Ballast Weights

Ballast should always be fitted when specified. Ballast must be of solid materials (i.e. not sand, water or other liquid or granular materials) and must be securely attached to the tower structure. Ballast weights placed at the base of the structure will increase tower self-weight, thereby increasing stability. Care must be taken to ensure that the weight of the ballast weights used is known, and that the total safe load on the structure, and particularly on the castors, is not exceeded. Use good manual handling techniques when handling ballast. See quantity schedule on pages 13 to 16 for ballast information.

Note: Ballast weights should be uniformly distributed to a maximum of 275kg per deck.

During assembly, use and dismantling

- As part of the risk assessment, wind conditions must be taken into account and reviewed regularly, depending on the duration the structure is onsite.
- The structure has been assessed for wind loads equating to 27mph (43kph, 12m/s).
- The effect of wind conditions onsite must be considered prior to the assembly of a tower. The tower must not be used in wind speeds beyond 27mph. If greater wind speeds are forecast, the tower must be dismantled while it is still safe to do so.
- Sheets, tarpaulins, cladding or similar, must not be attached to the tower as these will significantly increase any side loads from wind and will potentially make the tower unstable.
- Beware of wind turbulence, funnelling effects around buildings and updraughts on stairways.

The maximum allowable side load on a tower is 30kg.

- CAUTION: Excessive side loads due to working from the tower may cause the structure to become unstable. Special consideration should be given to side loads including vibrations.
- Do not abuse equipment. Damaged, incorrect or incompatible components should not be used.
- The structure is highly conductive and must not be used when there is a risk of lightning strikes.
- Exercise caution when touching unprotected metal components in extreme high or low temperatures.
- If the tower is damaged in any way while in service, it must not be used again until the damaged components are replaced.

Wind description	Beaufort scale	Beaufort no.	Speed in mph	Speed in m/sec
Medium Breeze	Raises dust and loose paper, twigs snap off	4	8-12	4-6
Strong Breeze	Large branches in motion, telegraph wires whistle	6	25-31	11-14
Gale Force	Walking is difficult	8	39-46	17-21

Ties

This structure is designed to be self-supporting under the loading condition requirements of BS 1139-6:2014 and does not require tying in. Consideration should be given to potential wind conditions if the tower is left unattended - see 'During Assembly, Use and Dismantling' section on page 7.

Tower designation & safety data


In accordance with the prefabricated tower scaffold standards, the 'Tower Designation & Safety Data' should be positioned at the base of the prefabricated tower scaffold as shown within the user guide, by means of the 'Tower Designation Information Assembly'. It must be clearly visible so that users are aware of the conditions of safe use. Refer to Safety Data Schedule for content.


Stabilisers

Stabilisers shall always be fitted when specified. See quantity schedule on pages 13 to 16

Attach one stabiliser to each corner of the tower as shown.

Position the lower clamp so that the lower arm is as close to horizontal as possible. Adjust the position of the upper clamp to ensure the stabiliser foot is in contact with the ground. Ensure clamps are secure. Telescopic stabilisers must always be fully extended.





	,
SP7	1227
SP10	2241
SP15	2757

Assembly Procedure

This tower structure must be assembled, and components oriented, in accordance with this user guide.

Deviation from this user guide is not permitted.

A minimum of two persons are recommend for assembly and disassembly of this prefabricated tower structure. The maximum number of persons permitted on the tower during assembly is stated in the safety data schedule.

Platforms must be installed with vertical distances between them not exceeding 2m when assembling and dismantling.

The maximum number of people on a working platform level permitted to simultaneously exert a horizontal load of 30kg is:

- 1 person per bay for bays less than 4m long
- 2 persons per bay for bays greater than 4m in length

Check that all components, tools and safety equipment are onsite (refer to quantity schedule), undamaged and that they are functioning correctly, particularly the brace claw locking mechanism.

Full inspection guidance can be found at www.bossaccesstowers.com.

Damaged or incorrect components should not be used.

Component weights can be found in the quantity schedule and on the corresponding BoSS Product Datasheets.

Check that the ground on which the tower structure is to be erected and moved is capable of supporting the tower in use and within the levelling limits of the tower system.

Check overhead that the area into which the tower structure is to be built contains no obstructions, particularly electrical or radio radiation hazards.

When positioning the tower take into account risk of collision with the tower e.g. from pedestrians, vehicles or doors. Secure doors (not fire exits) and windows where possible in the work area.


Never stand on an unguarded platform positioned above the first rung of a tower structure. If your risk assessment shows it necessary, you may also need to guardrail platforms at this level.

Assembly Procedure


Tower components should be lifted using a reliable lifting material (e.g. a strong rope) employing a reliable knot (e.g. clove hitch) to ensure safe fastening and always lift within the footprint of the tower structure.

'Tower Designation & Safety Data' content for the 'Tower Designation Information Assembly' can be found in the 'Safety Data Schedule'. This assembly must be positioned at the base of the prefabricated tower scaffold and clearly visible for users. Refer to Safety Data Schedule for content.

Adjustable legs should only be used for levelling purposes and never to gain extra height.



Ensure horizontal braces and guardrails are fitted correctly.



Ensure interlock clips on frame members are in the 'locked' position.


Assembly Procedure





Ensure wind-locks are engaged before moving onto the deck levels.

Component Diagram



BoSS Compact End Cantilever Tower Scaffold - 1.8m long main tower with 0.75m long cantilever

	33606200	8.2	6.2	9	9	1		3	-		3	-	-	2	1	4	19	16	2	4	3		4	2	-	-	9	2	2	2	-	-
	33605700	7.7	5.7	9	9	-	-	2	-	-	2	-	-	2	-	4	19	16	2	4	3		4	2	-	-	9	2	2	2	-	-
	33605200	7.2	5.2	9	9			3			9	-	-	2	-	4	19	14	2	4	3		4	2	-	-	9	2	2	2	-	-
	33604700	6.7	4.7	9	9		1	2		-	2	-	-	2	-	4	19	14	2	2	2		4	2	-	-	9	2	2	2	-	-
l use	33604200	6.2	4.2	9	9	-		2	-		2	-	-	2	-	4	15	12	2	4	2	4		2	-	-	9	2	2	2	-	-
rnal or externa	33603700	5.7	3.7	9	9	-	-	-	-	-	-	-	-	2	-	4	15	12	2	4	2	4			-	-	9	2	2	2	-	-
Inter	33603200	5.2	3.2	9	9			2			2	-	-	2	-	4	15	10	2	3	2	4			-	-	9	2	2	2	-	-
	33602700	4.7	2.7	9	9		-	-		-	-	-	-	2	1	4	15	10	2	4	1	4			-	-	9	2	2	2	-	-
	33602200	4.2	2.2	9	9	-		-	1		-	-	-	2	1	4	1	89	2	2	1	4			-	-	9	2	2	2	-	-
	33601200	3.2	1.2	9	9			1			-	-	1	2	1	2	11	4	2	2	1	4			-	-	9	2	2	2	-	-
	Composite code	Working height (m) >	Platform height (m) >	1.1kg	3.3kg	4.0kg	5.6kg	7.1kg	5.4kg	8.0kg	10.4kg	12.0kg	3.4kg	7.5kg	2.8kg	1.7kg	2.0kg	2.1kg	5.6kg	11.8kg	12.7kg	3.8kg	8.8kg	1.6kg	0.9kg	0.6kg	0.3kg	2.1kg	3.2kg	1.2kg		
		Component description and weight		Adjustable Leg	Ø150mm (6") Castor	Span Frame Mk2 - 1.0m - 2 Rung - 1450 Wide	Span Frame Mk2 - 1.5m - 3 Rung - 1450 Wide	Span Frame Mk2 - 2.0m - 4 Rung - 1450 Wide	Ladder Frame Mk3 - 1.0m - 2 Rung - 1450 Wide	Ladder Frame Mk3 - 1.5m - 3 Rung - 1450 Wide	Ladder Frame Mk3 - 2.0m - 4 Rung - 1450 Wide	Step -Through Multi-Purpose Ladder Frame	Guardrail Frame	Cantilever Frame	1.45m Cantilever End Beam Unit	1.45m Horizontal Brace	1.8m Horizontal Brace	2.1m Diagonal Brace	0.75m Fixed Deck	1.8m Fixed Deck	1.8m Trapdoor Deck	Stabiliser - SP7 - Saddle Blade Clamp	Stabiliser - SP10 - Saddle Blade Clamp	0.89m Brace Assembly	0.6m Infill Deck	0.3m Infill Deck	Toe Board Holder	1.45m End Toe Board	1.8m Side Toe Board	0.75m Side Toe Board	Tower Designation Information Kit	User Guide
		Component		33551300	32842300	60551300	60451300	60351300	61151300	61051300	60951300	39951300	63851400	34051300	35351300	34651300	31251300	31351300	30051100	30151100	30451100	31751300	31851300	34051600	35851100	35751100	30150900	30350900	30450900	30850900	30001900	03302300

Component Quantity &

Safety Data Schedule

Compact End Cantilever Tower Scaffold User Guide

Component Quantity & Safety Data Schedule

Max. No. of persons on any one platform unit 1 Max. No. of persons permitted on the lower during assembly and dismantling 1 Max. No. of simultaneous working platforms permitted 1 Max. No. of persons permitted on the working platform during use Highest working platform during use 1 Max. Ose Land 3 and 4 M. 9 M. of M. o									
	-		,						
- '		-	- '	-		-		E 1	
	1					١,			1 1 1
May Safe working load on the working alattern (log is dil)									
max. Sale working load on the working planoff. (kg d.d.)									
Highest working platform (kg u.d.l) 691 691		691	691	691	691		691	691 691	
2nd / 3rd / 4th / 5th / 6th Highest working platform (kg u.d.l)									
Max. Safe working load on the entire scaffold (kg u.d.l) 691 691		691	691	691	691		691	691 691	
Max. Working platform height for internal use (m) 1.2 2.2		2.7	3.2	3.7	4.2		4.7	4.7 5.2	
Max. Working platform height for external use (m) 1.2 2.2		2.7	3.2	3.7	4.2		4.7	4.7 5.2	
Design standard BS1139-6 BS1139-	3S1139-6 BS1139-6	BS1139-6	BS1139-6	BS1139-6	BS1139-6		BS1139-6	F	BS1139-6
Load class 3 3		3	3	3	က		3	3	3 3
Access class D D		٥	٥	۵	۵		۵	٥	
Clear height class		ī,	Ŧ,	±°	Ξ ^c		Ŧ,	T T	

NOTE

The safety data specified within the schedule above which relates to the specific tower to be assembled must be transferred into the pre-defined boxes on the Tower Designation Information insert found in the Tower Designation Information Kit.

BoSS Compact End Cantilever Tower Scaffold - 2.5m long main tower with 0.75m long cantilever

Component Quantity & Safety Data Schedule

						Inter	mal or externa	al use				
		Composite code	33701200	33702200	33702700	33703200	33703700	33704200	33704700	33705200	33705700	33706200
Component	Component description	Working height (m) >	3.2	4.2	4.7	5.2	2.7	6.2	6.7	7.2	7.7	8.2
		Platform height (m) >	1.2	2.2	2.7	3.2	3.7	4.2	4.7	5.2	5.7	6.2
33551300	Adjustable Leg	1.1kg	9	9	9	9	9	9	9	9	9	9
32842300	Ø150mm (6") Castor	3.3kg	9	9	9	9	9	9	9	9	9	9
60551300	Span Frame Mk2 - 1.0m - 2 Rung - 1450 Wide	4.0kg					-	1			-	-
60451300	Span Frame Mk2 - 1.5m - 3 Rung - 1450 Wide	5.6kg			-		-		-		-	
60351300	Span Frame Mk2 - 2.0m - 4 Rung - 1450 Wide	7.1kg	-	-	-	2	-	2	2	3	2	9
61151300	Ladder Frame Mk3 - 1.0m - 2 Rung - 1450 Wide	5.4kg		-			-	1			-	1
61051300	Ladder Frame Mk3 - 1.5m - 3 Rung - 1450 Wide	8.0kg			,		-		-		-	
60951300	Ladder Frame Mk3 - 2.0m - 4 Rung - 1450 Wide	10.4kg	-	-	-	2	-	2	2	3	2	3
39951300	Step-Through Multi-Purpose Ladder Frame	12.0kg	-	-	-	-	-	1	-	-	-	-
63851400	Guardrail Frame	3.4kg	-	-	-	-	-	1	-	-	-	-
34051300	Cantilever Frame	7.5kg	2	2	2	2	2	2	2	2	2	2
35351300	1.45m Cantilever End Beam Unit	2.8kg	-	-	-	-	-	-	-	-	-	-
34651300	1.45m Horizontal Brace	1.7kg	2	4	4	4	4	4	4	4	4	4
31251300	1.8m Horizontal Brace	2.0kg	4	4	4	4	4	4	4	4	4	4
31351300	2.1m Diagonal Brace	2.1kg	2	4	4	4	4	4	4	4	4	4
34851300	2.5m Horizontal Brace	2.4kg	7	7	11	11	1	11	15	15	15	15
31451300	2.7m Diagonal Brace	2.5kg	2	4	9	9	8	89	10	10	12	12
30051100	0.75m Fixed Deck	5.6kg	2	2	2	2	2	2	2	2	2	2
30151100	1.8m Fixed Deck	11.8kg	-	-	-	-	-	1	-	2	2	2
30251100	2.5m Fixed Deck	16.0kg	-	-	3	2	2	2	3	2	2	2
30551100	2.5m Trapdoor Deck	16.3kg	-	-	-	2	2	2	2	3	3	8
31751300	Stabiliser - SP7 - Saddle Blade Clamp	3.8kg	4	4	4	4	4	4				
31851300	Stabiliser - SP10 - Saddle Blade Clamp	8.8kg							4	4	4	4
34051600	0.89m Brace Assembly	1.6kg						2	2	2	2	4
35851100	0.6m Infill Deck	0.9kg	-	-	-	-	-	1	-	-	-	1
35751100	0.3m Infill Deck	0.6kg	1	-	-	-	-	1	1	-	-	1
30150900	Toe Board Holder	0.3kg	9	9	9	9	9	9	9	9	9	9
30350900	1.45m End Toe Board	2.1kg	2	2	2	2	2	2	2	2	2	2

Compact End Cantilever Tower Scaffold User Guide

Component Quantity & Safety Data Schedule

2	2	-	-	387	110	400	390	390	-	-	-		-			861		861	6.2	6.2	BS1139-6	3	۵	ī
2	2	-	-	380	96	355	390	390	-	-	-		-			861		861	5.7	5.7	BS1139-6	3	۵	ľ
2	2	-	-	369	80	310	380	380	-	-	-		-			861		861	5.2	5.2	BS1139-6	8	۵	Í
2	2	-	-	353	09	265	370	370	-	-	-		-			861		861	4.7	4.7	BS1139-6	3	۵	ľ
2	2	-	-	298	45	220	370	370	-	-	-		-			861		861	4.2	4.2	BS1139-6	3	۵	ī
2	2	-	-	291	40	195	360	360	-	-	-		-			861		861	3.7	3.7	BS1139-6	3	۵	Į
2	2	-	-	281	40	170	360	360	-	-	-		-			861		861	3.2	3.2	BS1139-6	3	۵	Í
2	2	-	-	277	32	145	350	350	-	-	-		-			861		861	2.7	2.7	BS1139-6	3	٥	ľ
2	2	-	-	226	30	120	340	340	-	-	-		-			861		861	2.2	2.2	BS1139-6	3	۵	
2	2	-	-	204	30	98	340	340	-	-	-		-			861		861	1.2	1.2	BS1139-6	3	۵	
4.4kg	1.2kg			Total Self-weight of tower (kg)	Ballast internal use (kg)	Ballast external use (kg)	Max. exerted leg load internal use (kg)	Max. exerted leg load external use (kg)	Max. No. of persons on any one platform unit	sembly and dismantling	ding platforms permitted	ting platform during use	Highest working platform during use	ting platform during use	rking platform (kg u.d.l)	Highest working platform (kg u.d.l)	rking platform (kg u.d.l)	entire scaffold (kg u.d.l)	ight for internal use (m)	ight for external use (m)	Design standard	Load class	Access class	Clear height class
2.5m Side Toe Board	0.75m Side Toe Board	Tower Designation Information Kit	User Guide	Total			Max. exerted l	Max. exerted le	Max. No. of persons	Max. No. of persons permitted on the tower during assembly and dismantling	Max. No. of simultaneous working platforms permitted	Max. No. of persons permitted on the working platform during use	Highest work	2nd / 3rd / 4th / 5th / 6th Highest working platform during use	Max. Safe working load on the working platform (kg u.d.)	Highest wo	2nd / 3rd / 4th / 5th / 6th Highest working platform (kg u.d.l)	Max. Safe working load on the entire scaffold (kg u.d.l)	Max. Working platform height for internal use (m)	Max. Working platform height for external use (m)				
30550900	30850900	30001900	03302300							Max. N														

The safety data specified within the schedule above which relates to the specific tower to be assembled must be transferred into the pre-defined boxes on the Tower Designation Information insert found in the Tower Designation Information Kit.

3.2m working platform height shown*



Build pattern - type 1 Tower working platform heights: 1.2m, 3.2m, 5.2m

3.7m working platform height shown*



Build pattern - type 2 Tower working platform heights: 3.7m, 5.7m

*Note: Decks and guardrails omitted from views for clarity.

2.2m working platform height shown*



Build pattern - type 3 Tower working platform heights: 2.2m, 4.2m, 6.2m

2.7m working platform height shown*



Build pattern - type 4 Tower working platform heights: 2.7m, 4.7m

*Note: Decks and guardrails omitted from views for clarity.

When building a BoSS tower

To comply with 'Work at Height Regulations' we show assembly procedures with platforms every two metres in height and the locating of guardrails in advance of climbing onto a platform to increase safety and reduce the risk of a fall. Never stand on an unguarded platform positioned above the first rung of a tower. If your risk assessment shows it necessary, you may also need to guardrail platforms at this level.

The procedure illustrated shows a 6.2m working height tower build.

For alternative tower height build patterns pages 17 and 18.


The manufacturer recommends two persons are used to build BoSS Towers. Above 4.0m platform height, it is essential that at least two persons are used. Only climb the tower from the inside.

The manufacturer recommend the 'Tower Designation & Safety Data' is recorded within the 'Tower Designation Information Assembly' before proceeding with the tower assembly. Refer to Safety Data Schedule for content.

Push castor into adjustable leg. Push castor/leg assembly into the 2 rung frame and lock the castor. Repeat for the other side of the frame. It is recommended, for ease of levelling, that a maximum gap of 50mm is left between the bottom of the leg and the adjustable nut.


Ensure all castors are locked.

Note: Adjustable legs are for levelling only. They are not to be used to gain extra height at the working level.



Fit one horizontal brace (red catch) onto the vertical of the 2 rung span frame, just below the bottom rung with the open section of the claw facing outwards.






Note: All locking claws must be opened before fitting and positively locked into position.

Repeat step 1 for the 2 rung ladder frame and position it as shown and fit the other end of the horizontal brace onto the vertical, just below the bottom rung of span frame. Fit the second horizontal brace between the bottom rungs on the other side of the frame to square the structure. Fit additional horizontal brace onto the vertical in position shown.

Ensure all claws are positively locked into position.

The structure must be vertical to within 1cm per metre.

Ensure the frames are vertical and level by checking with a spirit level and setting the adjustable legs as required.





Fit the 4 rung ladder frame and the 4 rung span frame to the structure base. Fit four diagonal braces in positions shown.


Ensure all claws are positively locked into position.

Ensure inbuilt ladders are aligned.

Record 'Tower Designation & Safety Data' within the 'Tower Designation Information Assembly' and attach to the tower in position shown. Refer to safety data schedule for content.

For alternative tower height build patterns see pages 17 and 18.





Ensure interlock clips on frame members are in the 'locked' position.

Fit the trapdoor deck and fixed deck on the fourth rungs of the tower. The trapdoor deck must be oriented such that the trapdoor opens towards the outside of the structure. Ensure the deck wind-locks are engaged.

From the protected trapdoor position, fit guardrails at 0.5m and 1.0m (in that order) above the platform level.

Do not climb on the deck until all guardrails are in place.

Ensure all claws are positively locked into position.

Ensure trapdoor is directly aligned with inbuilt ladder.



3T - Protected Trapdoor Position

Ensure all wind-locks are engaged.

6 Fit four stabilisers as shown, see page 8 for details. Telescopic stabilisers must always be fully extended.

Note: Position lower clamps so that the lower arm is as close to horizontal as possible. Adjust the position of the top clamp to ensure the stabiliser foot is in firm contact with the ground. Ensure clamps are secure.




Fit two castors with adjustable legs to the 4 rung span frame and link to the main frame using 1.8m horizontal and 2.1m diagonal braces. Fit fixed decks as shown to support ballast, refer to tables on page 25. Level the whole assembly and ensure castors are locked. Ensure all wind-locks are engaged.

Ensure all claws are positively locked into position.

Note: Ballast weights should be uniformly distributed to a maximum of 275kg per deck.

The tower must be vertical to within 1cm per metre.

For alternative tower height build patterns see pages 17 and 18.




	33606200	8.2	6.2	2
	33605700	7.7	5.7	2
	33605200	7.2	5.2	2
	33604700	6.7	4.7	2
ort ballast ing cantilevel	33601200 33602200 33602700 33603200 33603700 33604200 33604700 33605200 33605700 33606200	6.2	4.2	2
ecks to supp with 0.75M lo	33603700	2.7	3.7	2
ity of fixed d y main tower	33603200	5.2	3.2	_
Quant 1.8M long	33602700	4.7	2.7	_
	33602200	4.2	2.2	-
	33601200	3.2	1.2	_
	Composite code	Working height (m)	Platform height (m)	No. of fixed decks

4.7	1	3.2 4.2 4.7 5.2 5.7 6.2 6.7 7.2 7.7 8.2 1.2 2.2 2.7 3.2 3.7 4.2 4.7 5.2 5.7 6.2
3.2 3.7	3.5	2.7 3.2
	2.7	
3.2 4.2 1.2 2.2 1 1	1.2	

Fit the guardrail frame to the step-through multi-purpose ladder frame, ensuring all claws are positively locked into position and add the subassembly to the structure. Ensure that the guardrail opens inwards, as indicated with an arrow. Fit another 4 rung ladder frame and add two diagonal braces in positions shown. Fit two 0.89m brace assemblies.

Ensure inbuilt ladders are aligned.




Fit the fixed deck and trapdoor deck 2.0m above the previous level. Ensure all wind-locks are engaged. Note the orientation of the trapdoor. From the protected trapdoor position, fit guardrails at 0.5m and 1.0m (in that order) above the platform level. Fit two diagonal braces in positions shown. Fit two 1.45m horizontal braces to span frame, 0.5m and 1.0m below step-through multi-purpose ladder frame as shown.


Ensure all claws are positively locked into position.

Ensure trapdoor is directly aligned with inbuilt ladder as shown.

Do not climb on the deck until all guardrails are in place.



10 Fit two cantilever frames, as shown. Note position of couplers. Ensure wing nuts are fully tightened.




11 From the protected position within the main tower, fit the cantilever end beam unit. Ensure the claws touch on the ring.

Fit two 0.7m fixed decks, as shown. Ensure all wind-locks are engaged.


Fit two 1.45m horizontal braces as guardrails onto the middle and top rungs of cantilever frames.

Ensure all claws are positively locked into position.

Do not walk out onto the cantilever bay until it is fully assembled and all guardrails are in place.



Fit the 0.3m and 0.6m infill decks. Fit toe board holders and toe boards around edges of top decks, as shown. Store the guardrail frame at the base of the tower as shown.



To dismantle a BoSS tower:

Simply follow the assembly steps in reverse, ensuring that the 3T method is followed.

Pre-use Safety Inspection Checklist

Description	Yes
Tower structure upright and level	
Castors locked and legs correctly adjusted	
Horizontal and diagonal braces fitted	
Stabilisers and props fitted as specified	
Platforms located and wind-locks engaged	
Interlock clips engaged	
Toe boards located	
Infill decks fitted correctly	
Ballast fitted as specified	
Guardrails fitted correctly and positively locked	
Tower designation information kit fitted	

This checklist should be actioned at intervals determined by the manager. This checklist should also be actioned if the tower has been moved or modified, if any damage is suspected or if there are any changes to the local environment that may affect tower stability.

For further information about this product or any other products and services, please contact:

Blackwater Trading Estate, The Causeway, Maldon, Essex, CM9 4LJ, United Kingdom +44 (0)1621 745900

+44 (0)1621 859845

■ uk.customercare@wernerco.com ⊕ bossaccesstowers.com

Members of:

