



**Instruction Manual BS EN 1004-2:2021**  
The ALTO HD Linked Towers are certified to BS 1139-6:2022

## **3T - Through The Trapdoor Method**

### **Assembly guide using Base Jacks & Tied-In**



# Introduction

Please read these instructions carefully and ensure that you fully understand all of the information contained herein. All of the information in this document is vital for the safe utilisation of your Alto Heavy Duty Tower in Tied In Linked Tower applications.

These instructions only cover the assembly of this configuration of equipment, which is designed primarily for construction and maintenance tasks in a fixed position over a large area at platform heights of between 3m and 12m. All Alto Access products are professional quality engineered equipment designed primarily with safety in mind and meet or exceed all standards, recommendations and guidelines. Used properly, Alto access equipment will keep you safe when working at height.

This manual contains all of the information necessary to correctly assemble your Alto Heavy Duty mobile access tower equipment for this application in accordance with BS 1139-6:2022 and incorporates all of the requirements of the PASMA 3T method of assembly as endorsed by the HSE.

This manual should be used in conjunction with your Risk Assessment and Method Statement and in line with the Work at Height Regulations 2005 which place an obligation on employers to eliminate or minimise risks. This manual must be made available to the user/assembler at all pertinent times.

A Risk Assessment and Method Statement must be undertaken before installation commences and should include the relevant stabilisation to be applied to the specific structure being built in line with the guidance contained in this manual.

Only competent and qualified personnel should undertake erection, dismantling or alteration, organisation, planning or supervision of mobile access towers. In the case of any doubt, sufficient relevant additional training must be given beforehand to ensure safe use. For further information on the use of mobile access towers consult PASMA ([www.pasma.co.uk](http://www.pasma.co.uk); Tel +44 (0) 345 2 30 4041).

For any additional technical information or specific advice please contact the manufacturer Lakeside Industries Limited Tel: +44 1527 500577 or Email: [sales@altoaccess.com](mailto:sales@altoaccess.com).

## Certifications

The Alto Heavy Duty Tower is a mobile access tower certified to BS EN 1004-1:2020 Class 3. These instructions cover applications outside the scope of BS EN 1004-1:2020, within the scope of BS 1139-6:2022 to ensure that the configuration of the equipment meets the relevant requirements. This tower is manufactured in our ISO 9001 accredited facility. This manual complies with BS EN 1004-2:2021.

# Maximum Safe Working Loads

The safe working load of each bay of the tower is 1,500 kg including its own weight as it is to be assembled on base jacks. The maximum leg load imposed by the tower on its supporting surface is 750 kg when loaded to its maximum safe working load. The tower is a Class 3 tower.

The maximum safe working load of any individual platform unit within the tower is 324 kg evenly distributed.

The maximum safe uniformly distributed working load which may be placed on the working platform of the tower is 1,500 kg per bay over all the working platforms in use.

The maximum number of working platforms allowed in this configuration is 2.

The maximum number of operatives permitted on the tower during use is 12.

The maximum number of operatives permitted on the tower during assembly and dismantling is 8.

The maximum number of operatives permitted on any one platform unit is 2.

The maximum number of people on a working platform level permitted to simultaneously exert a horizontal load of 0.3 kN is 1 per bay.

If higher loadings are required, contact your supplier or the manufacturer - Lakeside Industries Limited, for advice. Tel: +44 1527 500577 or Email: [sales@altoaccess.com](mailto:sales@altoaccess.com).

## Inspection Care & Maintenance

Alto Access equipment is designed and manufactured to the highest standards in the industry and is stronger, more robust and safer than any comparable competitor product. Properly cared for, it will give a long and productive service life.

Inspection and maintenance guidance is published by the manufacturer for Alto HD equipment. This may be found here: [www.altoaccess.com/assets/inspection\\_hd.pdf](http://www.altoaccess.com/assets/inspection_hd.pdf)

ALTO HD Tower System equipment should not be modified in any way and should only be repaired by the manufacturer - Lakeside Industries Ltd - or by authorised agents. If it is suspected that equipment has been damaged, modified or repaired by any other provider, the equipment should be quarantined and returned to Lakeside Industries Ltd for free inspection. No liability will be accepted in relation to equipment that has been subjected to unauthorised modification or repair.

ALTO HD Tower System equipment is a robust product designed to operate in the construction industry environment. However, misuse or mishandling (including dropping or overloading or otherwise incorrectly using components) risks impairing the structural integrity of the components.

Components should be handled with care and stacked and secured safely whilst in transit.

Never use any equipment which is damaged, has parts missing or is improperly assembled.

## Safety

- This information shall be available at the location of use of the prefabricated tower scaffold.
- This prefabricated tower scaffold shall only be used according to this information.
- A risk assessment and method statement must be prepared sufficient to ensure the safe assembly, use and dismantling of a tied in linked tower structure and the elimination or minimisation of all consequent risks.
- Check that all of the necessary components, tools and equipment for the particular tower configuration to be built are on site, undamaged and functioning correctly. Damaged/incorrect components must not be used.
- BS 1139-6:2022 tower applications may only be used with 3T Alto towers. BS 1139-6:2022 tower applications may not be created using Advance Guard Rail (AGR) towers.
- This is a static tower. These instructions only cover the assembly of this specific structure on base jacks. If a mobile tower structure is required, contact the manufacturer Lakeside Industries Limited for advice Tel: +44 1527 500577 or Email: [sales@altoaccess.com](mailto:sales@altoaccess.com). This tower is not to be moved when built.
- Check that the surface on which the tower is to be located is capable of supporting the tower and its payload. Check that the level and slope of the ground do not render the location unsafe for the purposes of assembling, using and dismantling the tower.
- Beware obstructions when assembling, altering and dismantling the tower.
- When working outdoors, the weather forecast shall be taken into account before assembly, use and dismantling.
- Platforms must be installed with vertical distances between them not exceeding 2.1m when assembling and dismantling.
- Towers must always be climbed from the inside using the built in ladders (or Alto stair units if applicable). If the work carried out from the tower requires frequent carrying of equipment and materials up or down the tower, an Alto stair tower should be used in preference to a ladderspan tower.

- The tower must be levelled when erected using the adjustable jack legs.
- Four or more persons are required for the safe erection and dismantling of this tower.
- Always comply with the Work at Height Regulations 2005 when erecting, dismantling & using the tower.
- When lifting components, tools or materials, always use reliable lifting equipment and fastening methods and always lift from within the footprint of the tower structure to prevent risk of the tower overturning.
- Users must be aware of the effects of horizontal and vertical loads on the structure when using the tower which may impair the stability of the tower. Examples would be loads resulting from work on an adjacent structure or wind loads which may be increased by tunnelling effects around adjacent buildings.
- Beware live electrical installations, cables, moving machinery or other obstructions when erecting, dismantling or using the tower. The tower is a conductive metallic structure.
- Do not use boxes, ladders or other items to gain additional height.
- Do not stand on guard rails for any reason.
- If the tower is to be used in connection with hoisting arrangements, this requires specific advice from the manufacturer to ensure safety. Contact the manufacturer Lakeside Industries Limited for advice on loadings Tel: +44 1527 500577 or Email: [sales@altoaccess.com](mailto:sales@altoaccess.com).
- Prefabricated tower scaffolds in accordance with this standard are not designed to be lifted or suspended.
- When fitting platforms always engage wind latches.
- Fit guard rails to all Platforms.
- Fit toe boards to all Working Platforms.
- Every erected tower must be inspected at least every seven days and any tower which has been left unattended should be inspected before use to ensure that:
  1. No components have been removed or relocated incorrectly;
  2. The tower is still vertical; and
  3. No environmental or other factors have arisen which will influence safe use of the tower.
  4. the applied stabilisation methods and devices are still correctly positioned and operating effectively.
- Alto Access Products recommends the use of the PASMA TowerSure inspection system. For more information, please visit: [pasma.co.uk/towersure](http://pasma.co.uk/towersure)
- This tower is not to be sheeted.
- Alterations to the prefabricated tower are only permitted where they are shown in these instructions.

- User training courses cannot be a substitute for instruction manuals and assembly, use and dismantling plans but can only complement them.
- Only the components specified in this information shall be used.
- Damaged or incorrect components shall not be used.
- Prefabricated tower scaffolds designed in accordance with this standard are not anchor points for personal fall arrest equipment.
- Working is only permitted on a platform with a complete side protection including guardrails and toeboards.
- In the event that an alteration to the prefabricated tower scaffold design is required, approval from the supplier and/or designer shall be obtained and a revised instruction manual or assembly, user and dismantling plan created.
- When a prefabricated scaffold tower is used as a means of access to another place it shall:
  - » Be built on base plates
  - » Be tied in to the adjacent structure with ties of sufficient number and capacity to cope with a horizontal load of 10% of the maximum UDL of the working platform i.e. 2 kN.
  - » Be positioned so that any horizontal gap between the platform of the prefabricated scaffold tower and the place being accessed is no greater than 25 mm; and
  - » Be positioned so that the upper surface of the platform and surface which is being accessed are vertically aligned within a tolerance of  $\pm 25$  mm.
  - » Means of protection shall be removed only for the time and to the extent necessary to gain access or egress or for the performance of a particular task and shall be replaced as soon as practicable.
  - » Attention is drawn to the Work at Height Regulations 2005 Schedule 1, Schedule 2 Regulation 5 and Schedule 3 Part 1 Regulation 5.
  - » Provision shall be made to prevent falls – not only from the prefabricated tower scaffold, but also from the adjacent structure.
  - » The safety of persons once they have transferred to the adjacent place shall be taken into account as this now becomes a place of work at height.
  - » The strength of the adjacent place shall be assessed to verify that it is safe to step on to (e.g. not a fragile surface) and is a suitable and a safe place for work with adequate collective protection or other fall prevention measures.
  - » A prefabricated tower scaffold shall not be used as an anchor point for personal fall protection or work positioning equipment. They are not designed for this purpose even when tied to a supporting structure.

- » A prefabricated tower scaffold shall not be used as a means or element of edge protection. They are not designed or suitable for this purpose even when tied to a supporting structure. Edge protection shall be designed and installed in accordance with BS EN 13374.

## Wind Speeds

The weather forecast must be taken into account before assembly, use and dismantling. Persons using or responsible for towers must beware of the effect of wind on the structure. Wherever possible, as a precaution, it is advisable to tie the tower in to a rigid structure if it is to be used where it is exposed to potential windy conditions. Users should beware the potential tunnelling effect of open ended or unclad buildings and narrow openings between buildings. We recommend that the use of the tower is discontinued in conditions where the wind speed is above 17mph (force 4).

WIND DESCRIPTION	BEAUFORT SCALE	AVERAGE SPEED	INFORMATION
Medium Breeze	4	13-17 mph	Safe to work on tower.
Strong Breeze	6	25-31 mph	Tie the tower to a solid structure. Do not work on tower.
Gale Force	8	39-46 mph	Towers must be dismantled. Towers must not be assembled.

## Erecting & Dismantling the Tower


All BS 1139-6:2022 tower structures using Alto HD equipment must be built and dismantled in accordance with the step by step instructions set out below and having regard to the working at height regulations and Health & Safety legislation.

## 3T Method Explained

The “3T” or “through the trapdoor” method is one of the two permitted ways of assembling a tower without the assembler being at risk of falling. This tower is a 3T tower.


### Step 1:

As each new level of platform is installed, the operative takes up a working position in the trap door of the platform, standing on the ladder and leaning back against the edge of the trapdoor aperture.





### Step 2:

From this position the operative fits the horizontal braces 500mm and 1000 mm above the platform level (i.e. on the first and second available rungs). If the far end of the guardrail braces don't fully engage when they are put in place, the operative fully engages it when first climbing up onto the platform. This process ensures that operatives never have to stand on an unguarded platform.





## Braces

All braces are fitted with spring loaded pins that automatically lock the brace into position when attached to a tower. Brace hooks **must** be located either over the rung screw heads, between 2 screw heads or between the frame upright and a screw head to prevent lateral movement.




Diagonal braces **must** always be located with the claw opening facing down. Horizontal braces must be located with the claw facing either down (on the rung) or outwards (if on the upright).



# Frames

Almost all linked tower structures comprise of alternating “tower” & “bridge” sections. In Alto structures “odd” number bays are generally tower sections.

It is important to understand which bays are towers and which are bridges for the following reason: Frames must always be assembled with the offset conical head pointing inwards on “tower” bays.




## Stabilisation

When assembling linked towers, suitable stability solutions must be used. The following points must be observed:

- A Risk Assessment and Method Statement must be undertaken before installation commences and should include the relevant tying-in method and tying-in locations to be applied to the specific structure being built in line with the guidance contained in this manual.
- Never build linked towers without having adopted and correctly installed the permitted stability solution.
- The permitted stability solution is to securely tie the linked tower into an adjacent rigid structure capable of withstanding the forces that will be imposed upon it by the attachment of the tower.
- The tying in pattern should ensure that the uprights of the tower are tied in a minimum of every 4 metres, both laterally and vertically in an alternating pattern. In practice this means that every other lift is tied in. Additionally, both ends of the structure must be tied in at 4 metre intervals.
- Ties should be located close to a node. A node is a point where a frame rung, upright, horizontal and diagonal brace meet.
- If it is impracticable to tie the tower into a suitable adjacent rigid structure, users must contact the manufacturer Lakeside Industries Limited for advice on possible alternative solutions. Tel: +44 1527 500577 or Email: [sales@altoaccess.com](mailto:sales@altoaccess.com).
- When used, select and install anchors in concrete and masonry must be selected and installed in accordance with BS 8539.
- This prefabricated tower scaffold has been designed to be properly secured to a suitable adjacent supporting structure capable of withstanding the forces that will be imposed upon it by the

attachment of the tower. Devices for securing the tower must be simultaneously rigid in both tension and compression and capable of withstanding and transmitting the loads imposed by the tower to the supporting structure.

- Scaffold couplers and tubes used for tying in must comply with BS EN 74-1:2005 and BS EN 12811-2:2004 respectively.
- Linked Alto HD towers which are properly tied in to an adjacent rigid structure should be able to withstand all but the most extreme UK weather conditions.
- If ballast is necessary, it must be secured in position and made of rigid materials such as steel or concrete, but excluding liquids or granular materials.
- If users consider that ballast may be necessary, contact the manufacturer Lakeside Industries Limited for advice on quantities and locations. Tel: +44 1527 500577 or Email: [sales@altoaccess.com](mailto:sales@altoaccess.com).



## Unattended Towers

To prevent use by unauthorised persons of complete or incomplete towers when unattended, steps should be taken to prevent unauthorised access. Appropriate steps may include some or all of the following:

- Use of scaffold alarms.
- Suitable physical means such as barriers or site fencing to prevent access to the area immediately around the tower.
- Warning signs identifying the areas where access is not permitted should be displayed at the access points to area occupied by the tower.
- Attaching a well designed and correctly fitted ladder guard to the lowest levels of the tower.
- Appropriate site security.
- Towers which have been left unattended should be inspected before use as outlined on page 5 above.

## Signage

After assembly or alteration, the following minimum information shall be displayed on the prefabricated tower scaffold and be clearly visible from the ground (e.g. on a tag):

- The name and contact details of the responsible person.
- If the tower is ready for application or not.
- The load class and the uniformly distributed load.
- If the prefabricated tower scaffold is intended for indoors use only.
- The date of assembly.
- The maximum number of simultaneous working platforms permitted.
- The maximum number of persons permitted on the working platform(s) during use.
- The maximum number of persons permitted on the tower during assembly and dismantling.
- The maximum number of persons permitted on any one platform.
- The maximum safe working load on working platforms.
- The maximum safe working load on the prefabricated tower scaffold.
- The load class of the prefabricated tower scaffold.
- The maximum horizontal force permitted at the working platform(s).
- The maximum wind limits for working on the prefabricated tower scaffold.
- The maximum wind limits for the prefabricated tower scaffold.

# Component Schedule

Single width linked tower assembly using 1.8m towers & 2.7m link decks.

## Build Method 'A'

This schedule shows the parts required for each bay of linked tower structures for the heights shown assuming that access is required at one end of the structure only. Each structure is defined as a starter tower with any number of additional bays. Counting from the starter tower as "1", bays will either be even or odd numbers. The end bay will always be an odd number and the relevant part changes are shown to produce the correct end configuration. Parts table assumes one working level. For additional working levels, add toeboards and corner clips based on table quantities.

CODE	PART DESCRIPTION	Wt	4.4m Platform Height				6.4m Platform Height				8.4m Platform Height				10.4m Platform Height				12.4m Platform Height			
			Start Tower	Even Bay	Odd Bay	End Bay	Start Tower	Even Bay	Odd Bay	End Bay	Start Tower	Even Bay	Odd Bay	End Bay	Start Tower	Even Bay	Odd Bay	End Bay	Start Tower	Even Bay	Odd Bay	End Bay
2233	HD Adj. Swivel Base Jack	2.1	4		4		4		4		4		4		4		4		4		4	
2015	HD 0.8m Base Frame	9.6	1		1		1		1		1		1		1		1		1		1	
2222	HD 0.8m 5 Rung Ladder Frame	12.7	1		1		1		1		1		1		1		1		1		1	
2016	HD 0.8m Main Frame	8.3				1				2												5
2223	HD 0.8m 4 Rung Ladder Frame	11.5	1				2				3				4				5			
2019	HD 0.8m 1/2 Frame	4.3	1		1		1		1		1		1		1		1		1		1	
2225	HD 0.8m 2 Rung Ladder Frame	6.1	1		1		1		1		1		1		1		1		1		1	
2022	HD 0.8m Walkthru 'H' Frame	6.7	1		2	-1	2		4	-2	3		6	-3	4		8	-4	5		10	-5
2023	HD 0.8m Walkthru' Frame Gate	4.0	1		2	-1	2		4	-2	3		6	-3	4		8	-4	5		10	-5
2076	HD SAW Timber Toeboard End	1.7	1		1		1		1		1		1		1		1		1		1	
2069	HD 1.8m Timber Toeboard Side	5.0	2				2				2				2				2			
2086	HD 1.8m Timber T/B Side - Link Vers.	7.6			2				2				2				2				2	
2087	HD 2.7m Timber T/B Side - Link Vers.	8.1		2				2				2				2				2		
2074	HD Toeboard Corner Bracket	0.9	2			2	2			2	2			2	2			2	2			2
2079	HD Toeboard Inline Socket	0.5	2	2	2	-2	2	2	2	-2	2	2	2	-2	2	2	2	-2	2	2	2	-2
2040	HD 1.8m Brace	2.6	10		10		14		14		18		18		22		22		26		26	
2041	HD 2.7m Brace	3.6	2	10	2		3	14	3		4	18	4		5	22	5		6	26	6	
2080	HD 1.8m x 3 Rung Brace (Blue)	3.2	2		2		2		2		2		2		2		2		2		2	
2043	HD 1.8m Platform	14.4			1				2				3				4				5	
2201	HD 1.8m Trap Platform	15.0	2		1		3		1		4		1		5		1		6		1	
2044	HD 2.7m Platform	19.7		1				2				3				4				5		
2202	HD 2.7m Trap Platform	20.4		1				1				1				1				1		

TOTAL SELF WEIGHT OF TOWER (KGS)	148	94	148	0	199	128	198	-2	250	162	248	-5	302	197	298	-7	353	231	348	-10
----------------------------------	-----	----	-----	---	-----	-----	-----	----	-----	-----	-----	----	-----	-----	-----	----	-----	-----	-----	-----

# Component Schedule

Single width linked tower assembly using 1.8m towers & 2.7m link decks.

## Build Method 'B'

This schedule shows the parts required for each bay of linked tower structures for the heights shown assuming that access is required at one end of the structure only. Each structure is defined as a starter tower with any number of additional bays. Counting from the starter tower as "1", bays will either be even or odd numbers. The end bay will always be an odd number and the relevant part changes are shown to produce the correct end configuration. Parts table assumes one working level. For additional working levels, add toeboards and corner clips based on table quantities.

CODE	PART DESCRIPTION	Wt	4.9m Platform Height				6.9m Platform Height				8.9m Platform Height				10.9m Platform Height			
			Start Tower	Even Bay	Odd Bay	End Bay	Start Tower	Even Bay	Odd Bay	End Bay	Start Tower	Even Bay	Odd Bay	End Bay	Start Tower	Even Bay	Odd Bay	End Bay
2233	HD Adj. Swivel Base Jack	2.1	4		4		4		4		4		4		4		4	
2015	HD 0.8m Base Frame	9.6	1		1		1		1		1		1		1		1	
2222	HD 0.8m 5 Rung Ladder Frame	12.7	1		1		1		1		1		1		1		1	
2016	HD 0.8m Main Frame	8.3				1				2				3				4
2223	HD 0.8m 4 Rung Ladder Frame	11.5	1				1				1				1			
2018	HD 0.8m 3/4 Frame	6.3	1		1		1		1		1		1		1		1	
2224	HD 0.8m 3 Rung Ladder Frame	8.8	1		1		1		1		1		1		1		1	
2022	HD 0.8m Walkthru "H" Frame	6.7	1		2	-1	2		4	-2	3		6	-3	4		8	-4
2023	HD 0.8m Walkthru' Frame Gate	4.0	1		2	-1	2		4	-2	3		6	-3	4		8	-4
2076	HD SW Timber Toeboard End	1.7	1			1	1			1	1			1	1			1
2069	HD 1.8m Timber Toeboard Side	5.0	2				2				2				2			
2086	HD 1.8m Timber T/B Side - Link Vers.	7.6			2				2				2				2	
2087	HD 2.7m Timber T/B Side - Link Vers.	8.1		2				2				2				2		
2074	HD Toeboard Corner Bracket	0.9	2			2	2			2	2			2	2			2
2079	HD Toeboard Inline Socket	0.5	2	2	2	-2	2	2	2	-2	2	2	2	-2	2	2	2	-2
2040	HD 1.8m Brace	2.6	12		12		16		16		20		20		24		24	
2041	HD 2.7m Brace	3.6	2	12	2		3	16	3		4	20	4		5	24	5	
2080	HD 1.8m x 3 Rung Brace (Blue)	3.2	2		2		2		2		2		2		2		2	
2043	HD 1.8m Platform	14.4			1				2				3				4	
2201	HD 1.8m Trap Platform	15.0	2		1		3		1		4		1		5		1	
2044	HD 2.7m Platform	19.7		1				2				3				4		
2202	HD 2.7m Trap Platform	20.4		1				1				1				1		

TOTAL SELF WEIGHT OF TOWER (KGS)	157	101	158	0	197	135	208	-3	237	170	258	-5	277	204	308	-8
----------------------------------	-----	-----	-----	---	-----	-----	-----	----	-----	-----	-----	----	-----	-----	-----	----

# Component Schedule

Single width linked tower assembly using 1.8m towers & 2.7m link decks.

## Build Method 'C'

This schedule shows the parts required for each bay of linked tower structures for the heights shown assuming that access is required at one end of the structure only. Each structure is defined as a starter tower with any number of additional bays. Counting from the starter tower as "1", bays will either be even or odd numbers. The end bay will always be an odd number and the relevant part changes are shown to produce the correct end configuration. Parts table assumes one working level. For additional working levels, add toeboards and corner clips based on table quantities.

CODE	PART DESCRIPTION	Wt	5.9m Platform Height				7.9m Platform Height				9.9m Platform Height				11.9m Platform Height			
			Start Tower	Even Bay	Odd Bay	End Bay	Start Tower	Even Bay	Odd Bay	End Bay	Start Tower	Even Bay	Odd Bay	End Bay	Start Tower	Even Bay	Odd Bay	End Bay
2233	HD Adj. Swivel Base Jack	2.1	4		4		4		4		4		4		4		4	
2015	HD 0.8m Base Frame	9.6	1		1		1		1		1		1		1		1	
2222	HD 0.8m 5 Rung Ladder Frame	12.7	1		1		1		1		1		1		1		1	
2016	HD 0.8m Main Frame	8.3				1				2				3				4
2223	HD 0.8m 4 Rung Ladder Frame	11.5	1				2				3				4			
2018	HD 0.8m 3/4 Frame	6.3	1		1		1		1		1		1		1		1	
2224	HD 0.8m 3 Rung Ladder Frame	8.8	1		1		1		1		1		1		1		1	
2019	HD 0.8m 1/2 Frame	4.3	1		1		1		1		1		1		1		1	
2225	HD 0.8m 2 Rung Ladder Frame	6.1	1		1		1		1		1		1		1		1	
2022	HD 0.8m Walkthru 'H' Frame	6.7	1		2	-1	2		4	-2	3		6	-3	4		8	-4
2023	HD 0.8m Walkthru' Frame Gate	4.0	1		2	-1	2		4	-2	3		6	-3	4		8	-4
2076	HD SAW Timber Toeboard End	1.7	1			1	1			1	1			1	1			1
2069	HD 1.8m Timber Toeboard Side	5.0	2				2				2				2			
2086	HD 1.8m Timber T/B Side - Link Vers.	7.6			2				2				2				2	
2087	HD 2.7m Timber T/B Side - Link Vers.	8.1		2				2				2				2		
2074	HD Toeboard Corner Bracket	0.9	2			2	2			2	2			2	2			2
2079	HD Toeboard Inline Socket	0.5	2	2	2	-2	2	2	2	-2	2	2	2	2	2	2	2	-2
2040	HD 1.8m Brace	2.6	14		14		18		18		22		22		26		26	
2041	HD 2.7m Brace	3.6	2	14	2		3	18	3		4	22	4		5	26	5	
2080	HD 1.8m x 3 Rung Brace (Blue)	3.2	3		3		3		3		3		3		3		3	
2043	HD 1.8m Platform	14.4			1				2				3				4	
2201	HD 1.8m Trap Platform	15.0	3		2		4		2		5		2		6		2	
2044	HD 2.7m Platform	19.7		1				2				3				4		
2202	HD 2.7m Trap Platform	20.4		2				2				2				2		
TOTAL SELF WEIGHT OF TOWER (KGS)			191	129	192	0	243	163	242	-2	294	197	292	-5	345	232	342	-7

# Component Schedule

Single width linked tower assembly using 1.8m towers & 2.7m link decks.

## Build Method 'D'

This schedule shows the parts required for each bay of linked tower structures for the heights shown assuming that access is required at one end of the structure only. Each structure is defined as a starter tower with any number of additional bays. Counting from the starter tower as "1", bays will either be even or odd numbers. The end bay will always be an odd number and the relevant part changes are shown to produce the correct end configuration. Parts table assumes one working level. For additional working levels, add toeboards and corner clips based on table quantities.

			3.4m Platform Height			5.4m Platform Height			7.4m Platform Height			9.4m Platform Height			11.4m Platform Height							
CODE	PART DESCRIPTION	Wt	Start Tower	Even Bay	Odd Bay	End Bay	Start Tower	Even Bay	Odd Bay	End Bay	Start Tower	Even Bay	Odd Bay	End Bay	Start Tower	Even Bay	Odd Bay	End Bay				
2233	HD Adj. Swivel Base Jack	2.1	4		4		4		4		4		4		4		4					
2015	HD 0.8m Base Frame	9.6	1		1		1		1		1		1		1		1					
2222	HD 0.8m 5 Rung Ladder Frame	12.7	1		1		1		1		1		1		1		1					
2016	HD 0.8m Main Frame	8.3				1				2				3				4				
2223	HD 0.8m 4 Rung Ladder Frame	11.5	1				2				3				4							
2022	HD 0.8m Walkthru "H" Frame	6.7	1		2	-1	2		4	-2	3		6	-3	4		8	-4				
2023	HD 0.8m Walkthru' Frame Gate	4.0	1		2	-1	2		4	-2	3		6	-3	4		8	-4				
2076	HD SAW Timber Toeboard End	1.7	1			1	1			1	1			1	1			1				
2069	HD 1.8m Timber Toeboard Side	5.0	2				2				2				2							
2086	HD 1.8m Timber T/B Side - Link Vers.	7.6			2				2				2				2					
2087	HD 2.7m Timber T/B Side - Link Vers.	8.1		2				2				2				2						
2074	HD Toeboard Corner Bracket	0.9	2			2	2			2	2			2	2			2				
2079	HD Toeboard Inline Socket	0.5	2	2	2	-2	2	2	2	-2	2	2	2	-2	2	2	2	-2				
2040	HD 1.8m Brace	2.6	10		10		14		14		18		18		22		22					
2041	HD 2.7m Brace	3.6	3	10	3		4	14	4		5	18	5		6	22	6					
2043	HD 1.8m Platform	14.4			1				2				3				4					
2201	HD 1.8m Trap Platform	15.0	2		1		3		1		4		1		5		1					
2044	HD 2.7m Platform	19.7		1				2				3				4						
2202	HD 2.7m Trap Platform	20.4		1				1				1				1						
TOTAL SELF WEIGHT OF TOWER (KGS)			134	94	135	0	186	128	185	-2	237	162	235	-5	288	197	284	-7	340	231	334	-10

# Component Schedule

Single width linked tower assembly using 2.7m towers & 2.7m link decks

## Build Method 'A'

This schedule shows the parts required for each bay of linked tower structures for the heights shown assuming that access is required at one end of the structure only. Each structure is defined as a starter tower with any number of additional bays. Counting from the starter tower as "1", bays will either be even or odd numbers. The end bay will always be an odd number and the relevant part changes are shown to produce the correct end configuration. Parts table assumes one working level. For additional working levels, add toeboards and corner clips based on table quantities.

CODE	PART DESCRIPTION	Wt	4.4m Platform Height				6.4m Platform Height				8.4m Platform Height				10.4m Platform Height				12.4m Platform Height			
			Start Tower	Even Bay	Odd Bay	End Bay	Start Tower	Even Bay	Odd Bay	End Bay	Start Tower	Even Bay	Odd Bay	End Bay	Start Tower	Even Bay	Odd Bay	End Bay	Start Tower	Even Bay	Odd Bay	End Bay
2233	HD Adj. Swivel Base Jack	2.1	4		4		4		4		4		4		4		4		4		4	
2015	HD 0.8m Base Frame	9.6	1		1		1		1		1		1		1		1		1		1	
2222	HD 0.8m 5 Rung Ladder Frame	12.7	1		1		1		1		1		1		1		1		1		1	
2016	HD 0.8m Main Frame	8.3				1				2				3				4				5
2223	HD 0.8m 4 Rung Ladder Frame	11.5	1				2				3				4				5			
2019	HD 0.8m 1/2 Frame	4.3	1		1		1		1		1		1		1		1		1		1	
2225	HD 0.8m 2 Rung Ladder Frame	6.1	1		1		1		1		1		1		1		1		1		1	
2022	HD 0.8m Walkthru 'H' Frame	6.7	1		2	-1	2		4	-2	3		6	-3	4		8	-4	5		10	-5
2023	HD 0.8m Walkthru' Frame Gate	4.0	1		2	-1	2		4	-2	3		6	-3	4		8	-4	5		10	-5
2076	HD SW Timber Toeboard End	1.7	1			1	1			1	1			1	1			1	1			1
2070	HD 2.7m Timber Toeboard Side	7.8	2				2				2				2				2			
2087	HD 2.7m Timber T/B Side - Link Vers.	8.1		2	2			2	2			2	2			2	2			2	2	
2074	HD Toeboard Corner Bracket	0.9	2			2	2			2	2			2	2			2	2			2
2079	HD Toeboard Inline Socket	0.5	2	2	2	-2	2	2	2	-2	2	2	2	-2	2	2	2	-2	2	2	2	-2
2041	HD 2.7m Brace	3.6	10	10	10		14	14	14		18	18	18		22	22	22		26	26	26	
2042	HD 3.3m Brace	4.4	2		2		3		3		4		4		5		5		6		6	
2083	HD 2.7m x 3 Rung Brace (Black)	4.1	2		2		2		2		2		2		2		2		2		2	
2044	HD 2.7m Platform	19.7		1	1			2	2			3	3			4	4			5	5	
2202	HD 2.7m Trap Platform	20.4	2	1	1		3	1	1		4	1	1		5	1	1		6	1	1	

TOTAL SELF WEIGHT OF TOWER (KGS)	177	94	173	0	239	128	233	-2	300	162	293	-5	362	197	353	-7	424	231	413	-10
----------------------------------	-----	----	-----	---	-----	-----	-----	----	-----	-----	-----	----	-----	-----	-----	----	-----	-----	-----	-----

# Component Schedule

Single width linked tower assembly using 2.7m towers & 2.7m link decks

## Build Method 'B'

This schedule shows the parts required for each bay of linked tower structures for the heights shown assuming that access is required at one end of the structure only. Each structure is defined as a starter tower with any number of additional bays. Counting from the starter tower as "1", bays will either be even or odd numbers. The end bay will always be an odd number and the relevant part changes are shown to produce the correct end configuration. Parts table assumes one working level. For additional working levels, add toeboards and corner clips based on table quantities.

CODE	PART DESCRIPTION	Wt	4.9m Platform Height				6.9m Platform Height				8.9m Platform Height				10.9m Platform Height			
			Start Tower	Even Bay	Odd Bay	End Bay	Start Tower	Even Bay	Odd Bay	End Bay	Start Tower	Even Bay	Odd Bay	End Bay	Start Tower	Even Bay	Odd Bay	End Bay
2233	HD Adj. Swivel Base Jack	2.1	4		4		4		4		4		4		4		4	
2015	HD 0.8m Base Frame	9.6	1		1		1		1		1		1		1		1	
2222	HD 0.8m 5 Rung Ladder Frame	12.7	1		1		1		1		1		1		1		1	
2016	HD 0.8m Main Frame	8.3				1				2				3				4
2223	HD 0.8m 4 Rung Ladder Frame	11.5	1				1				1				1			
2018	HD 0.8m 3/4 Frame	6.3	1		1		1		1		1		1		1		1	
2224	HD 0.8m 3 Rung Ladder Frame	8.8	1		1		1		1		1		1		1		1	
2022	HD 0.8m Walkthru 'H' Frame	6.7	1		2	-1	2		4	-2	3		6	-3	4		8	-4
2023	HD 0.8m Walkthru' Frame Gate	4.0	1		2	-1	2		4	-2	3		6	-3	4		8	-4
2076	HD SW Timber Toeboard End	1.7	1			1	1			1	1			1	1			1
2070	HD 2.7m Timber Toeboard Side	7.8	2				2				2				2			
2087	HD 2.7m Timber T/B Side - Link Vers.	8.1		2	2			2	2			2	2			2	2	
2074	HD Toeboard Corner Bracket	0.9	2			2	2			2	2			2	2			2
2079	HD Toeboard Inline Socket	0.5	2	2	2	-2	2	2	2	-2	2	2	2	-2	2	2	2	-2
2041	HD 2.7m Brace	3.6	12	12	12		16	16	16		20	20	20		24	24	24	
2042	HD 3.3m Brace	4.4	2		2		3		3		4		4		5		5	
2083	HD 2.7m x 3 Rung Brace (Black)	4.1	2		2		2		2		2		2		2		2	
2044	HD 2.7m Platform	19.7		1	1			2	2			3	3			4	4	
2202	HD 2.7m Trap Platform	20.4	2	1	1		3	1	1		4	1	1		5	1	1	
TOTAL SELF WEIGHT OF TOWER (KGS)			189	101	185	0	239	135	245	-3	289	170	305	-5	339	204	365	-8

# Component Schedule

Single width linked tower assembly using 2.7m towers & 2.7m link decks

## Build Method 'C'

This schedule shows the parts required for each bay of linked tower structures for the heights shown assuming that access is required at one end of the structure only. Each structure is defined as a starter tower with any number of additional bays. Counting from the starter tower as "1", bays will either be even or odd numbers. The end bay will always be an odd number and the relevant part changes are shown to produce the correct end configuration. Parts table assumes one working level. For additional working levels, add toeboards and corner clips based on table quantities.

CODE	PART DESCRIPTION	Wt	5.9m Platform Height				7.9m Platform Height				9.9m Platform Height				11.9m Platform Height			
			Start Tower	Even Bay	Odd Bay	End Bay	Start Tower	Even Bay	Odd Bay	End Bay	Start Tower	Even Bay	Odd Bay	End Bay	Start Tower	Even Bay	Odd Bay	End Bay
2233	HD Adj. Swivel Base Jack	2.1	4		4		4		4		4		4		4		4	
2015	HD 0.8m Base Frame	9.6	1		1		1		1		1		1		1		1	
2222	HD 0.8m 5 Rung Ladder Frame	12.7	1		1		1		1		1		1		1		1	
2016	HD 0.8m Main Frame	8.3				1				2				3				4
2223	HD 0.8m 4 Rung Ladder Frame	11.5	1				2				3				4			
2018	HD 0.8m 3/4 Frame	6.3	1		1		1		1		1		1		1		1	
2224	HD 0.8m 3 Rung Ladder Frame	8.8	1		1		1		1		1		1		1		1	
2019	HD 0.8m 1/2 Frame	4.3	1		1		1		1		1		1		1		1	
2225	HD 0.8m 2 Rung Ladder Frame	6.1	1		1		1		1		1		1		1		1	
2022	HD 0.8m Walkthru' "H" Frame	6.7	1		2	-1	2		4	-2	3		6	-3	4		8	-4
2023	HD 0.8m Walkthru' Frame Gate	4.0	1		2	-1	2		4	-2	3		6	-3	4		8	-4
2076	HD S/W Timber Toeboard End	1.7	1			1	1			1	1			1	1			1
2070	HD 2.7m Timber Toeboard Side	7.8	2				2				2				2			
2087	HD 2.7m Timber T/B Side - Link Vers.	8.1		2	2			2	2			2	2			2	2	
2074	HD Toeboard Corner Bracket	0.9	2			2	2			2	2			2	2			2
2079	HD Toeboard Inline Socket	0.5	2	2	2	-2	2	2	2	-2	2	2	2	-2	2	2	2	-2
2041	HD 2.7m Brace	3.6	14	14	14		18	18	18		22	22	22		26	26	26	
2042	HD 3.3m Brace	4.4	2		2		3		3		4		4		5		5	
2083	HD 2.7m x 3 Rung Brace (Black)	4.1	3		3		3		3		3		3		3		3	
2044	HD 2.7m Platform	19.7		1	1			2	2			3	3			4	4	
2202	HD 2.7m Trap Platform	20.4	3	2	2		4	2	2		5	2	2		6	2	2	

TOTAL SELF WEIGHT OF TOWER (KGS)	231	135	221	0	293	169	281	-2	355	203	341	-5	416	238	401	-7
----------------------------------	-----	-----	-----	---	-----	-----	-----	----	-----	-----	-----	----	-----	-----	-----	----

# Component Schedule

Single width linked tower assembly using 2.7m towers & 2.7m link decks

## Build Method 'D'

This schedule shows the parts required for each bay of linked tower structures for the heights shown assuming that access is required at one end of the structure only. Each structure is defined as a starter tower with any number of additional bays. Counting from the starter tower as "1", bays will either be even or odd numbers. The end bay will always be an odd number and the relevant part changes are shown to produce the correct end configuration. Parts table assumes one working level. For additional working levels, add toeboards and corner clips based on table quantities.

CODE	PART DESCRIPTION	Wt	3.4m Platform Height				5.4m Platform Height				7.4m Platform Height				9.4m Platform Height				11.4m Platform Height			
			Start Tower	Even Bay	Odd Bay	End Bay	Start Tower	Even Bay	Odd Bay	End Bay	Start Tower	Even Bay	Odd Bay	End Bay	Start Tower	Even Bay	Odd Bay	End Bay	Start Tower	Even Bay	Odd Bay	End Bay
2233	HD Adj. Swivel Base Jack	2.1	4		4		4		4		4		4		4		4		4		4	
2015	HD 0.8m Base Frame	9.6	1		1		1		1		1		1		1		1		1		1	
2222	HD 0.8m 5 Rung Ladder Frame	12.7	1		1		1		1		1		1		1		1		1		1	
2016	HD 0.8m Main Frame	8.3				1				2				3				4				5
2223	HD 0.8m 4 Rung Ladder Frame	11.5	1				2				3				4				5			
2022	HD 0.8m Walkthru "H" Frame	6.7	1		2	-1	2		4	-2	3		6	-3	4		8	-4	5		10	-5
2023	HD 0.8m Walkthru Frame Gate	4.0	1		2	-1	2		4	-2	3		6	-3	4		8	-4	5		10	-5
2076	HD SW Timber Toeboard End	1.7	1		1	1	1		1	1	1		1	1	1		1	1	1		1	1
2070	HD 2.7m Timber Toeboard Side	7.8	2				2				2				2				2			
2087	HD 2.7m Timber T/B Side - Link Vers.	8.1		2	2			2	2			2	2			2	2			2	2	
2074	HD Toeboard Corner Bracket	0.9	2			2	2			2	2			2	2			2	2			2
2079	HD Toeboard Inline Socket	0.5	2	2	2	-2	2	2	2	-2	2	2	2	-2	2	2	2	-2	2	2	2	-2
2041	HD 2.7m Brace	3.6	10	10	10		14	14	14		18	18	18		22	22	22		26	26	26	
2042	HD 3.3m Brace	4.4	3		3		4		4		5		5		6		6		7		7	
2044	HD 2.7m Platform	19.7		1	1			2	2			3	3			4	4			5	5	
2202	HD 2.7m Trap Platform	20.4	2	1	1		3	1	1		4	1	1		5	1	1		6	1	1	
TOTAL SELF WEIGHT OF TOWER (KGS)			163	94	159	0	225	128	219	-2	286	162	279	-5	348	197	339	-7	409	231	399	-10

## ASSEMBLY INSTRUCTIONS - All Platform Heights

### Step 1

Insert the base jacks into the base of the 5 Rung Base Frame and 5 Rung Ladder Frame.



### Step 2

Connect 2 horizontal braces to the uprights of the first frame in the area just above the bottom rung. Make sure that the braces are connected from the inside of the tower facing outwards. Make sure that the frame head fittings are pointing inwards into the tower.



### Step 3

Connect the 2nd frame to the horizontal braces in the same position that they are located on the first frames. Make sure that the frame head fittings are pointing inwards into the tower.






#### Step 4

Connect 2 standard diagonal braces to the frames as shown. Keep the diagonal braces as close to the frame uprights as possible. Ensure that they run in opposite directions to each other.



#### Step 5

Install a trap platform on the 3rd rung up and 4 horizontal braces as guard rails. Using a spirit level, ensure that the framework is completely level by adjusting the legs. Twist the serrated collar on the base jack to adjust up & down.




#### Step 6

Connect a ladder frame & base jacks to the existing tower's plain frame using 2 horizontal braces. Head fittings on the new frame should point away from the 1st bay. Clip the braces on the bottom horizontal rungs of the frames. Make sure there is enough room on the new frame between the new brace hook & the frame upright to fit a diagonal brace & another horizontal brace when assembling the next bay.

**SAFETY NOTE:** One person should keep holding the new ladder frame upright until the next stage is in progress.

### Step 7

Now install a trap platform in-line with the previous bay's platform - orientated so the trap door is at the end by the ladder. Ensure the wind latches are fully engaged. Using either the 3T method or from the ground, clip on 4 horizontal braces to give the platform 4 guardrails. Now square and level the bay.



### Step 8

Repeat steps 2 to 7 until the required length of linked tower assembly has been created.



**For Build Method D - 3.4m; 5.4m; 7.4m; 9.4m; 11.4m - proceed to step 10. Otherwise, see the relevant build method below for the linked tower height required.**


## Build Method A – 4.4m, 6.4m, 8.4m, 10.4m, 12.4m



### Step 9.1

Working from the temporary platform on the starting tower, install 2 rung main and ladder frames in appropriate positions onto the 5 rung frames. Then, clip onto the top rung a coloured diagonal brace (blue or black). The other end connects to the 3rd rung down on the opposite frame. Diagonal braces always run parallel to the braces below.

Install another 4 guard rails above the 4 already in place for when the platform is relocated. Repeat this process all along the assembly.



### Step 9.2


Remove the lower 4 guardrails by either using the 3T method or uninstalling them from the ground. Then relocate the platform up 2 rungs to the top rung of the base frames all along the tower. Repeat this process all along the assembly.

Now proceed to Step 10.

## Build Method B – 4.9m, 6.9m, 8.9m, 10.9m


### Step 9.1

Working off the temporary platform on the first tower, install a 3 rung frame & a 3 rung ladder frame in appropriate positions onto the 4 rung frames. Clip onto the top rung a coloured diagonal brace (blue or black). The other end connects to the 3rd rung down on the opposite face. Diagonal braces always run parallel to the braces below. Repeat this process all along the assembly.




### Step 9.2

Relocate the platform down one rung and add an additional 2 braces in the position above the platform by either using the 3T method or working from the ground. Working off this, install a trap platform 4 rungs above. Repeat this process all along the assembly.




### Step 9.3

Using the 3T method, install 4 guardrails to the upper platform. The lower platform and the 4 guardrails can now be removed. Make sure that there are still 2 horizontal braces on the top rung of the base frames. Repeat this process all along the assembly.




Now proceed to Step 10.

## Build Method C – 5.9m, 7.9m, 9.9m, 11.9m




### Step 9.1

From the temporary platform on the starting tower, Install a 2 rung frame & a 2 rung ladder frame onto the base frames. Then, clip a coloured diagonal brace (blue or black) to the top rungs. The other end connects to the 3rd rung down on the opposite face. Now install another 4 guard rails above the 4 already in place for when the platform is relocated. Repeat this process all along the assembly.



### Step 9.2

Remove the lower 4 guardrails by using the 3T method or uninstalling them from the ground. Then relocate the platform to the top rung of the first frames. Working off this new platform location, install a 3 rung main frame and a 3 rung ladder frame. Then clip on a more coloured diagonal brace (blue or black) onto the top rung of the 3 rung frames. Repeat this process all along the assembly.



### Step 9.3

Lower the platform down 1 rung and relocate the guardrails into the correct positions using the 3T method. Install another set of trap platforms 4 rungs above the first platform. Then fit 4 guardrails using the 3T method. Repeat this process all along the assembly.

Now proceed to Step 10.

## All Platform Heights & Build Method D

### Step 10

Install the next level of frames. The one end of the run will always use 4 rung ladder frames. The opposite end of the run will always use 4 rung plain frames. The middle frames will always be 'H' frames with the gates fitted. Now, fit the correct diagonal braces in the positions shown.

*Build Method A = Blue/Black Braces*

*Build Method B = Blue/Black Braces*

*Build Method C = Blue/Black Braces*

*Build Method D = 2.7/3.3m Braces*




### Step 11

Now install the next level of platforms. Only use trap platforms where there is a vertical ladder in the frame. All other platforms are to be plain versions. Ensure all wind latches are fully engaged.

### Step 12

Starting from the ladder tower, using the 3T method, install 4 horizontal braces onto the top 2 rungs of the frames as shown.


Make sure the gate is installed in the walkthrough frame before fitting the braces.





### Step 13

Working from within the first bay, install the braces for the 2nd bay. Make sure that the braces connect to the frame uprights above the gate sockets. Once all the braces are completely engaged on the closest end, remove the panel inside the 'H' frame and store it safely until it is required again. Now, move to the opposite end and fully engage the braces.



### Step 14

Now repeat step 13 until all bays are fully guard railed. Ensure that the 'H' frame gate panel is kept in the frames until all 4 braces in the bay in front are engaged.

**At this point, install the appropriate tying in method for this level, as specified in the method statement. Refer to the "Tying In" section for more information.**



### Step 15

Repeat steps 10-14 until the final working platform height is established. Remember to install additional tying in as required by the specified tying in pattern as each relevant level is reached.

Finally, install the toeboards to all platforms on all working levels.


## DISMANTLING INSTRUCTIONS - All Platform Heights

The dismantling procedure is the reverse of the assembly procedure and requires a minimum of 2 operatives to complete the task safely. Particular points which must be followed during the dismantling include the following:

- Only ever disconnect tying-in methods from the highest level of the tower at any one time - immediately prior to the removal of that level.
- Remove the toeboard assembly from all working platform levels before removing that level of the tower.
- NEVER STAND ON AN UNGUARDED PLATFORM.


### Step 1

The dismantling procedure requires a minimum of 2 operatives to complete the task safely. To start, first remove the toeboard assembly from all working platform levels and disconnect the tying-in method from the highest level only.



### Step 2

Next, unclip the 4 guardrail brace hooks from the end frame ONLY. Ensure that all 4 brace hooks are still fully connected at the walkthrough frame end. Once all 4 braces are resting on the frame rung as shown, move directly back to the next bay.





### Step 3

Now install the Guard Rail Panel into the walkthrough 'H' Frame. Ensure that the panel is fully engaged and the spring loaded pins are fully located into the holes provided. At this point the panel should not be able to lift out without unlocking the pins.



### Step 4

Standing behind the walkthrough gate fitted in step 3, remove the 4 braces that were disconnected at the far end in step 2.



### Step 5

Repeat steps 2-4 until all bays except for the final bay has had the guardrails removed.


### Step 6

In the final bay, remove the 4 guardrails by first disconnecting each brace at the end furthest away from the platform trap door (as done in Step 2). Then immediately take up the protected position in the trap platform detailed in the 3T method. Whilst standing through the trapdoor as per the 3T method, disconnect the braces completely.



### Step 7


Now, working from the platforms below, the upper platforms can be removed along the whole structure.



### Step 8

The diagonal braces can now be taken off, followed by all the upper frames - as shown.

At this point, repeat steps 1-8 until the structure is dismantled or the new working platform height is achieved.



## NOTES

# Components



**2233** Swivel Base Jack



**2015** 0.8m Base Frame



**2016** 0.8m Main Frame



**2018** 0.8m 3/4 Frame



**2019** 0.8m 1/2 Frame



**2022** 0.8m Walkthrough  
Frame




**2023** 0.8m Walkthrough  
Frame Gate




**2222** 0.8m 5 Rung  
Ladder Frame



**2223** 0.8m 4 Rung  
Ladder Frame



**2224** 0.8m 3 Rung  
Ladder Frame



**2225** 0.8m 2 Rung  
Ladder Frame



**2040** 1.8m Brace



**2041** 2.7m Brace




**2042** 3.3m Brace




**2080** 1.8m x 3 Rung  
Brace (Blue)



**2083** 2.7m x 3 Rung  
Brace (Black)



**2043** 1.8m Plain Platform



**2201** 1.8m Trap Platform




**2044** 2.7m Plain Platform




**2202** 2.7m Trap Platform



**2069** 1.8m Timber  
Toeboard Side



**2070** 2.7m Timber  
Toeboard Side




**2076** S/W Timber  
Toeboard End




**2086** 1.8m Timber  
Toeboard Side - Linked



**2087** 2.7m Timber  
Toeboard Side - Linked



**2074** Timber Toeboard  
Corner Bracket



**2079** Timber Toeboard  
Inline Bracket

# THE HEIGHT OF SAFETY

For more information regarding our range of access products and services, please get in touch with us:

## Lakeside Industries Ltd

Unit 19 Howard Road, Park Farm Industrial Estate  
Redditch, Worcestershire. B98 7SE. UK

t: +44(0)1527 500 577

e: [sales@altoaccess.com](mailto:sales@altoaccess.com)

w: [www.altoaccess.com](http://www.altoaccess.com)



@lakesideindust



@altotowers



[lakeside-industries-ltd](https://www.linkedin.com/company/lakeside-industries-ltd)



Manufacturing Member

## Lakeside Industries Ltd

Unit 19 Howard Road, Park Farm Industrial Estate, Redditch, Worcestershire. B98 7SE  
+44(0)1527 500577 | [sales@altoaccess.com](mailto:sales@altoaccess.com) | [www.altoaccess.com](http://www.altoaccess.com)

